



## MONMOUTH COUNTY

### Construction Phase for Rumson-Sea Bright Bridge S-32 Replacement on Rumson Road (County Route 520) over the Shrewsbury River Borough of Rumson and Borough of Sea Bright, New Jersey

#### Public Notice

#### Shrewsbury River Waterway Navigational Channel – Temporary Width Reduction

Release Date: May 27, 2022

On or about July 1, 2022, weather permitting, the Contractor will begin bridge replacement activity in the Shrewsbury River. Temporary access trestles will be built on each side of the river, which the Contractor will use to construct the new bridge to the south of the existing bridge.

- The existing 75' wide navigational channel will continue to be open to mariners.
- The bridge operator will instruct vessels, as is currently done, when there are scheduled bridge openings.
- The existing bridge will continue to be open to vehicles and pedestrians.

On or about July 30, 2022, weather permitting, the Contractor will construct two temporary cofferdams, one adjacent to each trestle, which will reduce the navigational channel from 75' to 65' in width for an estimated 12-month duration.

- The 65' navigational channel will continue to be open to mariners.
- The bridge operator will instruct vessels, as is currently done, during this period when the channel is reduced by 10' in width.
- The existing bridge will continue to be open to vehicles and pedestrians.

On or about July 30, 2023, weather permitting, the Contractor will remove the cofferdams and restore the navigational channel from 65' to 75' in width.

- The restored 75' navigational channel will continue to be open to mariners.
- The bridge operator will instruct vessels, as is currently done, when there are scheduled bridge openings.
- The existing bridge will continue to be open to vehicles and pedestrians.

A 6-to-8-day full channel closure will be required later in 2023 for installation of the new drawbridge span. After the full closure, there will be a short-term restriction to half the channel width. Once traffic shifts to the newly constructed bridge, the old bridge will be closed for demolition. The access trestles to the south side of the bridge will be removed, and temporary access trestles will be constructed to the north for removal of the old bridge. The demolition work is estimated to occur in the early part of 2024. A separate public notice will be provided in the future to inform mariners and the public.

Please note - if any temporary disruption of access through the navigational channel occurs the information will be posted to the Travel Advisory page of the project website at [www.rumsonseabrightbridge.com/travel-advisory](http://www.rumsonseabrightbridge.com/travel-advisory).

There is also a link to the USCG Local Notice to Mariners under Useful Links, found in the upper right corner of the project website home page ([www.rumsonseabrightbridge.com](http://www.rumsonseabrightbridge.com)).

Questions or comments can be submitted by June 30, 2022 to:

- Monmouth County Project Manager by e-mail to [info@rumsonseabrightbridge.com](mailto:info@rumsonseabrightbridge.com) or by selecting the Contact Us tab on the project website ([www.rumsonseabrightbridge.com](http://www.rumsonseabrightbridge.com)),
- or
- USCG via e-mail to [D01-SG-BridgesD1obr-NY@uscg.mil](mailto:D01-SG-BridgesD1obr-NY@uscg.mil).

To sign up for the Rumson-Sea Bright Bridge S-32 Replacement project email list, go to the Contact Us section of the project website ([www.rumsonseabrightbridge.com/contact/#section-3](http://www.rumsonseabrightbridge.com/contact/#section-3)).

Thank you for your continued support and understanding during the construction phase of this important bridge replacement.

Regards,  
Rumson-Sea Bright Bridge S-32 Project Team

---

Contact Information

**Andrés Roda, P.E.**  
County Project Manager  
Monmouth County Division of Engineering  
Hall of Records Annex, 1 East Main Street  
Freehold, NJ 07728  
732-431-7760  
[info@rumsonseabrightbridge.com](mailto:info@rumsonseabrightbridge.com)

**Joseph M. Ettore, P.E.**  
Monmouth County Engineer