




PRELIMINARY AND FINAL SITE PLAN OF BLOCK 15 LOT 3 FOR 1080 OCEAN AVENUE BOROUGH OF SEA BRIGHT, MONMOUTH COUNTY, NJ



ZONE MAP
SCALE: 1"=300'



TAX MAP/AREA MAP
SCALE: 1"=200'



KEY/200' STRUCTURE MAP
SCALE: 1"=100'

200' ADJOINING OWNERS

BLOCK	LOT	QUAL.	CLA.	PROPERTY OWNER	PROPERTY LOCATION	AMT. LOTS
14	1	X	4A	FIRST UNITED METH. CHURCH SEA BRIGHT, NJ 07740	1104 OCEAN AVENUE	
14	2		1	CHURCH STREET CONDO ASSOCIATION 1 CHURCH STREET UNIT A SEA BRIGHT, NJ 07740	1 CHURCH STREET UNIT A	
14	2.01		2	KNOXON, JONAS A. CHEPIL 2.01 CHURCH STREET UNIT A SEA BRIGHT, NJ 07740	1 CHURCH STREET UNIT A	
14	2.02		2	COCKFIELD, JOE A. BABA 2.02 CHURCH STREET UNIT B SEA BRIGHT, NJ 07740	1 CHURCH STREET UNIT B	
14	3		2	MCCLUNEY, SEAN A. AMANDA K. 3 CHURCH STREET SEA BRIGHT, NJ 07740	3 CHURCH STREET	
14	4		2	MCCLUNEY, SEAN A. AMANDA K. 4 CHURCH STREET SEA BRIGHT, NJ 07740	4 CHURCH STREET	
14	5		2	DOMO, BERNARD A. CYNTHIA 5 CHURCH STREET SEA BRIGHT, NJ 07740	5 CHURCH STREET	
14	17		2	LOHMEYER, JAMES A. 17 SOUTH STREET SEA BRIGHT, NJ 07740	8 SOUTH STREET	
14	18		2	BEVIE REAL PROPERTIES LLC 18 SOUTH STREET SEA BRIGHT, NJ 07740	8 SOUTH STREET	
14	19		2	FOI, DAVID & PRIYA 19 SOUTH STREET SEA BRIGHT, NJ 07740	9 SOUTH STREET	
14	20		2	MOY, ROBERT K. II & SANDRA C. 20 SOUTH STREET SEA BRIGHT, NJ 07740	3 SOUTH STREET	
14	21		4A	WINDY RIDGES LLC 21 SOUTH STREET SEA BRIGHT, NJ 07740	1096 OCEAN AVENUE	
15	1		4A	WALLACE & KRISTIN, LLC 1 RIVER STREET MONMOUTH BEACH, NJ 07750	1092 OCEAN AVENUE	
15	2		4A	BEACHSIDE PGE, LLC 2 RIVER STREET SEA BRIGHT, NJ 07740	1084 OCEAN AVENUE	
15	4		4A	RIVER STREET REALTY, LLC 4 RIVER STREET SEA BRIGHT, NJ 07740	4 RIVER STREET	
15	5		4A	C. J. & M. ASSOC OF SEA BRIGHT, 5 RIVER STREET KINGSTON, NJ 08528	1100 RIVER STREET	6 & 7
15	8		2	JEFFREY A. HOWARD & SONS INC 8 SOUTH STREET SEA BRIGHT, NJ 07740	9 SOUTH STREET	
15	1		4A	1074 OCEAN, LLC 1074 OCEAN AVENUE SEA BRIGHT, NJ 07740	1074 OCEAN AVENUE	
15	2		4A	1072 SEA BRIGHT, LLC 1072 OCEAN AVENUE SEA BRIGHT, NJ 07740	1072 OCEAN AVENUE	
15	3		4A	1070 MONMOUTH PLACE 1070 OCEAN AVENUE SEA BRIGHT, NJ 07740	1070 OCEAN AVENUE	
15	4		4A	AMCK, LLC 1066 OCEAN AVENUE SEA BRIGHT, NJ 07740	1066 OCEAN AVENUE	
15	4.01		4A	TREZZA REALTY HOLDING LLC 1068 OCEAN AVENUE SEA BRIGHT, NJ 07740	1068 OCEAN AVENUE	
15	5		4A	1062 OCEAN AVENUE 1062 OCEAN AVENUE SEA BRIGHT, NJ 07740	1062 OCEAN AVENUE	
15	6		4A	1060 OCEAN AVENUE LLC 1060 OCEAN AVENUE SEA BRIGHT, NJ 07740	1060 OCEAN AVENUE	
15	14		2	MARTIN, IVAN WENAT 14 BADINGTON COURT SEA BRIGHT, NJ 07740	2 BADINGTON COURT	
15	15.01		1	ASSESSED WITH BLOCK 16 LOTS 15-23 15.01 AS PART OF COMMON ELEMENTS SEA BRIGHT, NJ 07740	2 BADINGTON COURT	
15	15.02		4A	MONMOUTH BOARDING CLUB, LLC 15.02 OCEAN AVENUE SEA BRIGHT, NJ 07740	1071 OCEAN AVENUE	
15	15.03		2	MURRO, ROBERT P. JR. 15.03 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 1	
15	15.04		2	MURRO, ROBERT P. JR. 15.04 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 2	
15	15.05		2	MURRO, ROBERT P. JR. 15.05 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 3	
15	15.06		2	MURRO, ROBERT P. JR. 15.06 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 4	
15	15.07		2	MURRO, ROBERT P. JR. 15.07 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 5	
15	15.08		2	MURRO, ROBERT P. JR. 15.08 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 6	
15	15.09		2	MURRO, ROBERT P. JR. 15.09 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 7	
15	15.10		2	MURRO, ROBERT P. JR. 15.10 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 8	
15	15.11		2	MURRO, ROBERT P. JR. 15.11 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 9	
15	15.12		2	MURRO, ROBERT P. JR. 15.12 WILDFIELD LAKE LAKE NORTH, NJ 07740	2 BADINGTON COURT UNIT 10	
15	24		2	JOHNSON, LESLIE A. & HUTTON, MAE E. 24 RIVER STREET SEA BRIGHT, NJ 07740	15 RIVER STREET	
15	25		2	15 RIVER STREET, LLC 15 RIVER STREET SEA BRIGHT, NJ 07740	15 RIVER STREET	
15	26		2	FOURMAN, JOHN ROBERT ETAL 26 RIVER STREET SEA BRIGHT, NJ 07740	9 RIVER STREET	
15	27		2	GOTTI, JOHN R. 27 RIVER STREET SEA BRIGHT, NJ 07740	11 RIVER STREET	
15	28		2	RIVER S, LLC 28 RIVER STREET SEA BRIGHT, NJ 07740	5 RIVER STREET	
23	1		11C	1000 OCEAN AVENUE 1000 OCEAN AVENUE SEA BRIGHT, NJ 07740	1000 OCEAN AVENUE	
23	2.02		11C	1051 OCEAN AVENUE 1051 OCEAN AVENUE SEA BRIGHT, NJ 07740	1051 OCEAN AVENUE	

GENERAL NOTES:

- APPLICANT/OWNER: THE BREAK AT SEA BRIGHT, LLC
MR. TRIP BROOKS
305 BOND STREET
SUITE #301
ASBURY PARK, NJ 07712
- THE PROPERTY IS KNOWN AS LOT 3, BLOCK 15 AS SHOWN ON THE OFFICIAL TAX MAP SHEET NO. 8 OF THE BOROUGH OF SEA BRIGHT, MONMOUTH COUNTY, NEW JERSEY.
 - SURVEY AND BOUNDARY INFORMATION SHOWN HEREIN TAKEN FROM MAP ENTITLED "SURVEY OF PROPERTY" PREPARED BY LANDMARK SURVEYING & ENGINEERING, INC., ZENON T. GRYBOWSKI, NJ PLS No. 23918, DATED 12/14/17, REVISED 1/12/18. UTILITY AND TOPOGRAPHIC LOCATIONS SUPPLEMENTED BY WJH ENGINEERING, PETER P. BENNETT III, NJ PLS No. 40651, DATED 9/27/19. TOPOGRAPHIC INFORMATION IS BASED ON NAVD 88.
 - SITE LOCATED IS LOCATED IN FLOOD ZONE "AE" (MIN. FLOOD ELEV. 8.0) PURSUANT TO PRELIMINARY FLOOD INSURANCE MAP #34025C0201F, DATED 9/25/09.
 - EXISTING USE: VACANT
 - PROPOSED USE: 6 CONDOMINIUMS AND 1 RETAIL SPACE (2,800 SF)
 - THE SITE IS CURRENTLY SERVED BY PUBLIC WATER AND SEWER.
 - DO NOT SCALE DRAWINGS AS THEY PERTAIN TO ADJACENT AND SURROUNDING PHYSICAL CONDITIONS, BUILDINGS, STRUCTURES, ETC.. THEY ARE SCHEMATIC ONLY, EXCEPT WHERE DIMENSIONS ARE SHOWN THEREIN.
 - THIS SET OF PLANS HAS BEEN PREPARED FOR PURPOSES OF MUNICIPAL AND AGENCY REVIEW AND APPROVAL. THESE PLANS SHALL NOT BE UTILIZED AS CONSTRUCTION DOCUMENTS UNTIL ALL CONDITIONS OF APPROVAL HAVE BEEN SATISFIED ON THE DRAWINGS AND EACH DRAWING HAS BEEN REVISED TO INDICATE "ISSUED FOR CONSTRUCTION".
 - EXISTING UTILITY INFORMATION SHOWN HEREON HAS BEEN COLLECTED FROM VARIOUS SOURCES AND IS NOT GUARANTEED AS TO ACCURACY OR COMPLETENESS. THE CONTRACTOR SHALL VERIFY ALL INFORMATION TO HIS SATISFACTION PRIOR TO EXCAVATION, AND NOTIFY NJ ONECALL AS REQUIRED BY LAW. TEST PIT INFORMATION SHALL BE GIVEN TO THE ENGINEER PRIOR TO CONSTRUCTION TO PERMIT ADJUSTMENT AS REQUIRED TO AVOID CONFLICTS. EXISTING UTILITY CONNECTIONS WILL BE UTILIZED, IF POSSIBLE.
 - ALL MATERIALS, WORKMANSHIP, AND CONSTRUCTION FOR SITE IMPROVEMENTS SHOWN HEREON SHALL BE IN ACCORDANCE WITH:
 - N.J. DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", AS CURRENTLY AMENDED.
 - CURRENT, PREVAILING MUNICIPAL AND/OR COUNTY SPECIFICATIONS, STANDARDS AND REQUIREMENTS.
 - CURRENT, PREVAILING UTILITY COMPANY/AUTHORITY SPECIFICATIONS, STANDARDS AND REQUIREMENTS.
 - CONTRACTOR SHALL NOTIFY THE UNDERSIGNED PROFESSIONAL IMMEDIATELY IF ANY FIELD CONDITIONS ENCOUNTERED DIFFER MATERIALLY FROM THOSE REPRESENTED HEREON AND/OR IF SUCH CONDITIONS, IN THE CONTRACTOR'S OPINION WOULD OR COULD RENDER THE DESIGN SHOWN HEREON INAPPROPRIATE OR INEFFECTIVE.
 - CONTRACTOR SHALL COORDINATE ANY UTILITY RELOCATIONS.
 - THIS PLAN IS SUBJECT TO ALL LOCAL AND STATE REGULATORY PERMITS, AGENCY REVIEW AND APPROVAL.
 - RETAIL & CONDO. REFUSE AND RECYCLING WILL BE HANDLED THROUGH A PRIVATE COMPANY AND STORED WITHIN THE GARAGE AND FIRST FLOOR AREAS.
 - IT IS THE INTENT OF THESE PLANS TO PROVIDE THE FOLLOWING GRADING CRITERIA:
 - 3:1 MAX.
 - 2% MIN. GRASS, 1% PAVEMENT
 - 6% MAX. WITHIN 10' OF PROPOSED BUILDINGS
 - THE OWNER, OR HIS REPRESENTATIVE, IS TO DESIGNATE AN INDIVIDUAL RESPONSIBLE FOR CONSTRUCTION SITE SAFETY DURING THE COURSE OF SITE IMPROVEMENTS PURSUANT TO N.J.A.C. 5:23-2.21(e) OF THE N.J. UNIFORM CONSTRUCTION CODE AND CFR 1926.321(f) (OSHA COMPETENT PERSON).
 - ALL SITE IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE BOROUGH OF SEA BRIGHT CONSTRUCTION STANDARDS, WHERE APPLICABLE.
 - FIRE ZONE SIGNAGE, STRIPING, KNOX BOX, ETC. SHALL BE IN ACCORDANCE WITH THE BOROUGH FIRE OFFICIAL.
 - SEPARATE UTILITY PERMIT APPLICATIONS MAY BE REQUIRED FOR LOCAL AGENCY FOR WATER & SEWER.
 - ALL ROOF LEADERS SHALL BE DIRECTED TOWARD THE STREET SYSTEM. LOAD ZONE: NOT REQUIRED.
 - ALL ELECTRIC, CABLE & TELEPHONE SERVICES TO BE INSTALLED UNDERGROUND FROM ADJACENT UTILITY POLE.
 - BUILDING FOOTPRINT DIMENSIONS OBTAINED FROM ARCHITECTS ON 9/25/20 AND SHOWN HEREON ARE APPROXIMATE. FINAL BUILDING FOOTPRINT DIMENSIONS SHALL BE FURNISHED AT TIME OF BUILDING PERMIT AND SHALL CONFORM TO APPROVED BULK STANDARDS.
 - ALL BONDS MUST BE POSTED PRIOR TO BUILDING PERMITS.
 - STREET LIGHTING SHALL MATCH EXACTLY TO ACORN LIGHTS, 16" FIXTURES LOCATED ON OCEAN AVENUE PROVIDED BY JCP&L.
 - ARCHITECT TO COORDINATE SIGNAGE PURSUANT TO BOROUGH ORDINANCES.
 - SIDEWALKS AND CURBS, IF DAMAGED, SHALL BE REPLACED. PROVISION TO PROVIDE PUBLIC CIRCULATION SHALL BE MAINTAINED AT ALL TIMES.

PRELIMINARY AND FINAL SITE PLAN OF BLOCK 15 LOT 3 FOR

1080 OCEAN AVENUE
BOROUGH OF SEA BRIGHT,
MONMOUTH COUNTY, NJ

JOB NUMBER 19181



CERT. OF AUTH. NO. 24G28117300
257 MONMOUTH ROAD, BLDG. A, STE. 7, OAKHURST, NJ 07755
PHONE - 732-223-1313

WALTER JOSEPH HOPKIN
N.J. PROFESSIONAL ENGINEER, LIC. No. 40673

Walter Joseph Hopkin

ZONING TABLE			
ZONE DISTRICT: B-1	BUSINESS DISTRICT		
	REQUIRED	EXISTING	PROPOSED
MINIMUM LOT AREA (S.F.)	3,000	4,674.76	4,674.76
MINIMUM LOT WIDTH (FT.)	50	55.00	55.00
MINIMUM LOT DEPTH (FT.)	60	85.00	85.00
MINIMUM FRONT YARD SETBACK (FT.)	0'-0"	N/A	0.00
MINIMUM SIDE YARD SETBACK (FT.)	0'-0"	N/A	0.00
MINIMUM REAR YARD SETBACK (FT.)	15'-0"	N/A	0.00*
MINIMUM GROSS FLOOR AREA (S.F.)	880	N/A	2,800
MAXIMUM BUILDING HEIGHT (FT.)	42	N/A	SEE ARCH. PLANS
MAXIMUM BUILDING COVERAGE AREA (%)	50	N/A	97*
MAXIMUM IMPERVIOUS COVERAGE (%)	75	100	97*
PARKING SPACES (SEA BRIGHT) RESIDENTIAL -----	2 SPACES / UNIT 12 REQUIRED	N/A	11 + 1 Handicap
* RETAIL/RESTAURANT -----	3 PEOPLE / SPACE 1 / EMPLOYEE	MUNICIPAL LOT	60 OCCUPANCY 8 EMPLOYEES 28 SPACES REQ.
PARKING SIZE: STANDARD	8.5' x 18' min.	-	9' x 18'

* VARIANCE REQUIRED

SHEET INDEX			
SHEET NO.	SHEET TITLE	ORIG. ISSUE DATE	LATEST REV. DATE
1	COVER SHEET	10/1/20	11/23/20
2	EXISTING CONDITIONS & DEMOLITION PLAN	10/1/20	11/23/20
3	DIMENSION PLAN	10/1/20	11/23/20
4	GRADING, DRAINAGE & UTILITY PLAN	10/1/20	11/23/20
5	CONSTRUCTION DETAILS	10/1/20	11/23/20

ATTORNEY:
KEVIN KENNEDY, ESQ.
165 STATE HWY. NO. 35
RED BANK, NJ 07701
PH. (732) 936-1099
kennedyjlaw@kevinkennedyjlaw.net

ARCHITECT:
DANIEL M. CONDATORE, R.A.
- MODE -
MONMOUTH OCEAN DESIGN EXPERTS
619 LAKE AVENUE
3RD. FLOOR
ASBURY PARK, NJ 07712
PH. (732) 800-1958

APPLICANT / OWNER:
THE BREAK AT SEA BRIGHT, LLC
TRIP BROOKS
305 BOND STREET
SUITE #301
ASBURY PARK, NJ 07712
PH. (732) 804-0902
TripBrooks@gmail.com

AS OWNER OF THE LANDS SHOWN ON THIS MAP, I/WE HEREBY
CONSENT TO FILE THIS MAP.

TRIP BROOKS _____ DATE _____

MONMOUTH COUNTY PLANNING
BOARD APPROVAL TO BE AFFIXED


CERTIFICATION:
APPROVED BY THE PLANNING BOARD OF THE BOROUGH OF SEA BRIGHT
MONMOUTH COUNTY, NEW JERSEY

CHAIRMAN _____ DATE _____


SECRETARY _____ DATE _____

CITY ENGINEER _____ DATE _____


W:\Projects\19181 - The Break at Ocean Ave. - Sea Bright\DWG\Design\Drawings\02-04 - SITE BASE.dwg 10/23/2020 2:42:26 PM




- LEGEND**
- GAS VALVE
 - WATER VALVE
 - WATER METER
 - UTILITY MANHOLE
 - DRAINAGE MANHOLE
 - ELECTRICAL MANHOLE
 - SANITARY MANHOLE
 - TELEPHONE MANHOLE
 - TRAFFIC SIGN
 - TRAFFIC SIGN (2 POST)
 - STREET SIGN
 - LIGHT POST
 - UTILITY POLE
 - FIRE HYDRANT
 - DRAINAGE INLET (TYPE 'A')
 - DRAINAGE INLET (TYPE 'B')
 - DRAINAGE INLET (TYPE 'E')
 - DRAINAGE LINE
 - ELECTRIC LINE
 - GAS LINE
 - SANITARY SEWER LINE
 - TELEPHONE LINE
 - WATER LINE
 - OVERHEAD WIRES
 - MONITORING WELL
 - IRON PIPE FOUND
 - CAPPED REBAR FOUND
 - CONCRETE MONUMENT FOUND
 - SURVEY
 - FILE MAP
 - GAS METER
 - D.C. DEPRESSED CURB
 - FLUSH CURB



1	11/23/20	GENERAL REVISIONS	JUL
NO.	DATE	DESCRIPTION	DRAWN BY
PRELIMINARY & FINAL SITE PLAN			
OF			
LOT 3 BLOCK 15			
BOROUGH OF SEA BRIGHT		MONMOUTH COUNTY	
NEW JERSEY			
WH ENGINEERING	CERT. OF AUTH. NO. 246A28117300 257 MONMOUTH ROAD, BLDG. A, STE. 7, OAKHURST, NJ 07795 PHONE-732-223-1313 WWW.WHENGINEERING.COM		EXISTING CONDITIONS & DEMOLITION PLAN
			WALTER JOSEPH HOPKIN N.J. PROFESSIONAL ENGINEER, LIC. No. 40673
SCALE: 1" = 10'	DRAWN BY: JUL	DATE: 10/1/20	JOB No.: 19181
		SHEET No.:	2 of 5



- LEGEND**
- GAS VALVE
 - WATER VALVE
 - WATER METER
 - UTILITY MANHOLE
 - DRAINAGE MANHOLE
 - ELECTRICAL MANHOLE
 - SANITARY MANHOLE
 - TELEPHONE MANHOLE
 - TRAFFIC SIGN
 - TRAFFIC SIGN (2 POST)
 - STREET SIGN
 - LIGHT POST
 - UTILITY POLE
 - FIRE HYDRANT
 - DRAINAGE INLET (TYPE "A")
 - DRAINAGE INLET (TYPE "B")
 - DRAINAGE INLET (TYPE "C")
 - DRAINAGE LINE
 - ELECTRIC LINE
 - GAS LINE
 - SANITARY SEWER LINE
 - TELEPHONE LINE
 - WATER LINE
 - OVERHEAD WIRES
 - MONITORING WELL
 - IRON PIPE FOUND
 - CAPED REBAR FOUND
 - CONCRETE MONUMENT FOUND
 - SURVEY
 - FILE MAP (FM)
 - GAS METER
 - DEPRESSED CURB
 - FLUSH CURB




NO.	DATE	DESCRIPTION	DRAWN BY
1	11/23/20	GENERAL REVISIONS	J.J.L.

PRELIMINARY & FINAL SITE PLAN
OF
LOT 3 OF BLOCK 15
BOROUGH OF SEA BRIGHT MONMOUTH COUNTY NEW JERSEY

	CERT. OF AUTH. NO. 246A28117300 257 MONMOUTH ROAD, BLDG. A, STE. 7, OAKHURST, NJ 07795, PHONE-732-229-1313 WWW.WJENGINEERING.COM	DIMENSION PLAN WALTER JOSEPH HOPKIN N.J. PROFESSIONAL ENGINEER, J.I.C. No. 40673
	SCALE: 1" = 10' DRAWN BY: JUL DATE: 10/1/20 JOB No.: 19181 SHEET No.: 3 of 5	

W:\Projects\19181 - The Break at Ocean Ave. - Sea Bright\DWG\Design\Drawings\02-04 - SITE PLAN.dwg 11/23/2020 12:13:26 PM

W:\Projects\19181\19181 - The Break at Ocean Ave., Sea Bright\DWG\Design Drawings\02-04 - SITE BASE.dwg 11/23/20 1:42:31 PM




LEGEND

	GAS VALVE
	WATER VALVE
	WATER METER
	UTILITY MANHOLE
	DRAINAGE MANHOLE
	ELECTRICAL MANHOLE
	SANITARY MANHOLE
	TELEPHONE MANHOLE
	TRAFFIC SIGN
	TRAFFIC SIGN (2 POST)
	STREET SIGN
	LIGHT POST
	UTILITY POLE
	FIRE HYDRANT
	DRAINAGE INLET (TYPE 'A')
	DRAINAGE INLET (TYPE 'B')
	DRAINAGE INLET (TYPE 'E')
	DRAINAGE LINE
	ELECTRIC LINE
	GAS LINE
	SANITARY SEWER LINE
	TELEPHONE LINE
	WATER LINE
	OVERHEAD WIRES
	MONITORING WELL
	IRON PIPE FOUND
	CAPPED REBAR FOUND
	CONCRETE MONUMENT FOUND
	SURVEY
	FILE MAP
	GAS METER
	D.C. DEPRESSED CURB
	F.C. FLUSH CURB

SEWER & WATER NOTES:


- Detailed interior sanitary sewer piping for the apartment buildings will be provided upon completion of the architectural plans.
- HVAC condensate shall not enter the wastewater system.
- The Sewer Authority shall witness all work associated with the proposed lateral connections to the existing DIP located within River Street.
- Water service to be provided from the existing eighteen (18) inch water service unless flow test reveals that the four (4) inch water line is capable of providing fire and domestic services. A flow test must be performed in order to finalize the connections.
- Pipe materials connections shall comply with local water company specifications. Water shutoff valves shall be color coded for fire and domestic.



1		11/23/20	GENERAL REVISIONS	JUL
NO.	DATE	DESCRIPTION		DRAWN BY
PRELIMINARY & FINAL SITE PLAN OF LOT 3 BLOCK 15 BOROUGH OF SEA BRIGHT MONMOUTH COUNTY NEW JERSEY				
		CERT. OF AUTH. NO. 24GA28117300 257 MONMOUTH ROAD, BLDG. A, STE. 7, OAKHURST, NJ 07795 PHONE-732-223-1313 WWW.WJHENGINEERING.COM		
		GRADING, DRAINAGE & UTILITY PLAN WALTER JOSEPH HOPKIN PROFESSIONAL ENGINEER, LIC. No. 40673		
SCALE:	DRAWN BY:	DATE:	JOB No.:	SHEET No.:
1" = 10'	JUL	10/1/20	19181	4 of 5

KNOX **KNOXBOX™ 3200**

The KnoxBox 3200 is the number one high-security key lock box trusted by first responders and property owners. Store up to 10 keys to quickly gain rapid access to commercial properties.



FEATURES

- Stores maximum 10 keys. Access cards and small entry items may also fit in interior compartment but will reduce max key quantity.
- Built Knox-Plugged and secure. UL 1037, UL 1610, UL 1300, UL 437
- Finished with Knox-Coat™ to protect four times better than standard powder coating.
- Weather-resistant door gasket
- Hinged door

BENEFITS

- Allows rapid property access
- Reduces property damage
- Prevents forced entry into buildings
- Minimizes first responder injury
- Compliant to National Fire Code (NFPA, IFC, IBC)

ACCESSORIES

- Multi Purpose Switch for use on electrical doors, gates and other electrical equipment
- Recess Mounting Kit for new concrete or masonry construction
- Public Safety Labels
- Tag-Out Tamper Seals
- Key Tags
- Key Rings

ORDERING SPECIFICATIONS

To insure promptment and delivery of the KnoxBox 3200, it is suggested that the following specification paragraph be used:

KnoxBox surface/recessed mount with hinged door, without UL Listed Knox Tamper Alert. 1/2" plate steel housing, 1/2" thick steel door with interior padded seal and stainless steel door hinge. Box and lock UL Listed. Lock has 150" thick stainless steel dust cover with tamper seal mounting capability.


Exterior Dimensions: Surface Mount Body - 4" x 5" x 3-7/8"
 Recessed Mount Flange - 7" x 4" x 1-1/2"
 Lock: UL Listed. Double-action rotating tumblers and hardened steel pins accessed by a braided cut key.
 Finish: Knox-Coat proprietary finishing process
 Color: Black, Dark Bronze or Aluminum
 PIN: KnoxBox 3200 (PIN's call. ID)
 Mfr's Name: KNOX COMPANY

1601 W. DEER VALLEY RD. PHOENIX, AZ 85027 | 1.800.552.5669 | 623.687.2290 | INFO@KNOXBOX.COM | KNOXBOX.COM

KNOX **KNOXBOX™ 3200**


GENERAL MOUNTING INSTRUCTIONS

Suggested minimum mounting height, 6 feet above ground.



RECESS MOUNTING KIT AND INSTALLATION INSTRUCTIONS

The Recess Mounting Kit (RMK) includes shell housing and mounting hardware, which may only be used for recessed models to cast-in-place within new concrete or masonry construction. The KnoxBox is mounted into the shell housing after construction is completed.




ABOUT KNOX COMPANY

Over forty years ago, a unique concept in rapid access for emergency response was born. The KnoxBox, a high-security key lock box, was designed to provide rapid access for emergency responders to reduce response times and protect property from forced entry.

Today, one revolutionary lock box has grown into a complete system providing rapid access for public safety agencies, industries, military, and property owners across the world. The Knox Company is trusted by over 14,000 fire departments, law enforcement agencies, and governmental entities.


KNOX COMPANY
 1601 W. DEER VALLEY RD
 PHOENIX, AZ 85027
 1.800.552.5669
 623.687.2290
 KNOXBOX.COM
 INFO@KNOXBOX.COM




TYPICAL SIGN POST DETAIL
NOT TO SCALE

NOTES:


- ALL REGULATORY & WARNING SIGNS SHALL BE HIGH INTENSITY REFLECTIVE SHEETING.
- ALL OTHER SIGNS SHALL BE ENGINEER GRADE SHEETING.
- ALL SIGNS AFFECTING COUNTY ROAD TRAFFIC SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST EDITION.
- SIGN POSTS SHALL BE 3LBS./FT.




HANDICAP PARKING SIGN DETAIL
N.T.S.




BRICK SIDEWALK PAVER DETAIL
NOT TO SCALE




HANDICAP STRIPING DETAIL
VAN ACCESSIBLE
NOT TO SCALE



HANDICAP PARKING DETAIL
NOT TO SCALE




CONCRETE DRIVEWAY APRON DETAIL
NOT TO SCALE




TYPICAL WATER SERVICE CONNECTION INSTALLATION
N.T.S.


- SERVICE PIPE TO BE 3/4" MINIMUM P.E. FLEX TUBING 160 LB. MUNICIPAL WATER SERVICE TYPE WITH C.T.S. (COPPER TUBE SIZE) O.D.
- CORPORATION COCK TO BE 3/4" PACTJOINT TYPE SIMILAR TO FORD F100 OR APPROVED EQUAL.
- CURB STOP TO BE 3/4" PACTJOINT TYPE SIMILAR TO FORD B44-333 OR 266-333 OR APPROVED EQUAL.
- COUPLINGS TO BE 3/4" PACTJOINT TYPE SIMILAR TO FORD C44-333 OR APPROVED EQUAL.
- LOCATION OF CURB STOP AND BOX TO BE IN PLANTER AREA OR ONE (1) FOOT ON RESIDENT'S SIDE OF PROPOSED SIDEWALK AND NEVER OUTSIDE OF STREET R.O.W.
- NO DEVIATION FROM THESE SPECIFICATIONS SHALL BE MADE WITHOUT APPROVAL OF THE GOVERNING AUTHORITY.
- NO CONNECTION WILL BE BACK-FILLED UNTIL WRITTEN APPROVAL IS MADE BY THE GOVERNING AUTHORITY.
- VIOLATORS WILL BE REQUIRED TO EXPOSE THE WORK FOR INSPECTION BEFORE APPROVAL WILL BE GRANTED.




ON-SITE CONCRETE CURB DETAIL
NOT TO SCALE



CONCRETE SIDEWALK DETAIL
NOT TO SCALE




SANITARY SEWER SERVICE LATERAL AND CLEANOUT DETAIL
NOT TO SCALE




WHEEL STOP DETAIL
NOT TO SCALE

GENERAL NOTES:


- CONCRETE USED TO HAVE MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3500 P.S.I.
- UNIT TO BE PINNED TO SURFACE WITH 3-3/4" DIA. STEEL RODS, 24" MINIMUM LENGTH.
- ALL BEVELS TO BE 1/2". 4. ALL ANGLES TO BE 45°.



DEPRESSED CURB DETAIL
NOT TO SCALE



HANDICAP RAMP DETAIL
NOT TO SCALE




DETECTABLE WARNING SURFACE DETAIL
NOT TO SCALE

GENERAL NOTES:

- THE DETAILS PROVIDED ARE NOT DRAWN TO SCALE. THE QUANTITY OF DOMES DEPICTED ON THE DETECTABLE WARNING FIELD (THE DOMES AND THE ENTIRE 2' LEVEL SURFACE) IS FOR ILLUSTRATION ONLY.
- LOCATION OF DETECTABLE WARNINGS: DETECTABLE WARNINGS SHALL BE LOCATED SO THAT THE EDGE OF THE WARNING FIELD NEAREST TO THE ROADWAY OR STREET SURFACE IS 8" TO 12" FROM THE TRANSVERSE CURB IS USED FROM THE EDGE OF THE ROADWAY/STREET, OR FROM THE FACE OF THE DROPPED CURB, WHERE A DROPPED CURB CONTIGUES ACROSS THE BOTTOM OF THE SIDEWALK CURB RAMP. THE DETECTABLE WARNINGS SHALL EXTEND THE FULL WIDTH OF THE CURB RAMP FLUSH SURFACE.
- DOME ALIGNMENT: DOMES SHALL BE ALIGNED ON A SQUARE GRID IN THE PRECEDENT DIRECTION OF TRAVEL.

NOTE: CONTRACTOR SHALL CONSULT "CURRENT" ADA STANDARDS PRIOR TO CONSTRUCTION.



HANDICAPPED PARKING SYMBOL
NOT TO SCALE

PRELIMINARY & FINAL SITE PLAN				
LOT 3 OF BLOCK 15				
BOROUGH OF SEA BRIGHT		MONMOUTH COUNTY		NEW JERSEY
1	11/23/20	GENERAL REVISIONS		JUL
NO.	DATE	DESCRIPTION		DRAWN BY
CONSTRUCTION DETAILS WALTER JOSEPH HOPKIN N.J. PROFESSIONAL ENGINEER, LIC. NO. 40673				
SCALE:	DRAWN BY:	DATE:	JOB No.:	SHEET No.:
AS NOTED	JUL	10/1/20	19181	5 OF 5